



Kevin Carrillo
469 222 1802
contact@backyardsolutionsgroup.com

March 17, 2026

Item	Description	Quantity	Price	Amount
Underground Plumbing Leak-Repair (Concrete Access & Restoration)	Repair of existing underground leak previously identified by another company. This service includes saw-cutting and breaking the existing concrete deck as needed to access the damaged pipe, repairing or replacing the failed plumbing section, pressure testing the repair, and restoring the concrete area after completion.	1	\$2,100	\$2,100
Pool Expansion Joint Removal & New Mastic Installation	Remove all existing deteriorated pool mastic from the expansion joint between the pool coping and surrounding deck. Joint will be properly cleaned and prepped before installing new self leveling pool grade mastic to allow for movement, prevent water intrusion, and protect the pool structure and deck.	1	\$975	\$975
Skimmer Removal & Replacement (2) (Optional)	Removal of two existing pool skimmers and installation of two new replacement skimmers. Includes cutting concrete as required, reconnecting plumbing lines, proper sealing and alignment, pressure testing, and restoring surrounding	1	\$2,800	\$2,800

	concrete and deck areas affected by the replacement.			
Full Pool Replaster Mini Pebble Finish	Complete resurfacing of the pool interior using a mini-pebble plaster finish. Includes draining the pool, surface prep, bond coat (primer) application, installation of mini-pebble interior finish, acid wash, cleanup, and refill coordination. Provides improved durability, texture, and long-term performance compared to standard plaster.	1	\$9,700	\$9,700
6"x6" Waterline Tile Removal/Intallation	Removal and disposal of existing waterline tile around the pool perimeter. Surface will be cleaned and prepared for proper bonding. Installation of new 6" x 6" basic porcelain waterline tile using appropriate pool-grade thinset and mortar. Joints will be properly aligned and finished with pool-rated grout to create a sealed and durable waterline. Work includes standard tile materials, installation labor, and cleanup of the work area.	1	\$2,400	\$2,400

Subtotal	\$17,975.00
Sales Tax:	\$0.00
Total Amount:	\$17,975.00

Disclaimer & Important Notes

•Leak Location Disclaimer

The underground plumbing repair scope is based on information provided by the client and/or findings from a third-party inspection company. Accessing the plumbing requires breaking existing concrete in the identified area to repair the suspected damaged pipe. If, after repair, the leak is determined to originate from a different location or component not included in this scope, additional diagnostics, demolition, plumbing repairs, and concrete restoration may be required and will be quoted separately.

•Plaster Chipping Contingency

This proposal does not include chipping or removal of existing plaster, as it may not be necessary. Once the pool is drained and the interior surfaces are fully visible, areas of hollow, delaminated, or compromised plaster may be identified. If plaster removal is recommended to achieve proper adhesion and long term performance of the new finish, this additional service may range approximately \$500–\$1,500, depending on the extent required. Final determination will be made after draining and inspection, and approval will be required prior to proceeding.

•Startup & Chemical Balancing Disclaimer

This proposal does not include pool startup or ongoing chemical balancing following the mini-pebble plaster installation. A proper pebble plaster startup is critical and must be performed immediately after the pool is filled to protect the new finish.

The startup process typically includes controlled filling of the pool without interruption, initial brushing of the plaster surface, chemical balancing of water (including pH, alkalinity, calcium hardness, and sanitizers), filtration management, and daily monitoring during the initial curing period. This process is commonly handled by the person responsible for pool maintenance.

Improper or delayed startup may result in discoloration, scaling, streaking, or reduced lifespan of the plaster finish. Startup services, if requested, can be provided separately or coordinated with a third-party pool service at an additional cost.

Scope of Work

1. Underground Plumbing Leak Repair & Concrete Restoration

- Saw-cut and remove existing concrete deck as required to access the suspected underground plumbing leak
 - Expose damaged plumbing section and perform repair or replacement of failed pipe and fittings
 - Pressure test repaired plumbing line to confirm integrity
 - Backfill excavated area with appropriate material and compact
 - Pour and finish concrete patch to restore affected deck area to match existing surface as closely as possible
-

2. Skimmer Removal & Replacement (Qty: 2)

- Remove two existing pool skimmers
 - Cut and remove concrete as necessary to access skimmer bodies and plumbing connections
 - Install two new pool skimmers with proper alignment and sealing
 - Reconnect plumbing lines and pressure test skimmer plumbing
 - Restore concrete and surrounding deck areas impacted by skimmer replacement
-

3. Pool Expansion Joint Preparation & New Mastic Installation

- Remove all existing deteriorated mastic from the expansion joint between pool coping and deck
 - Clean and prepare joint to ensure proper adhesion
 - Install new pool-grade self-leveling mastic designed to allow expansion and prevent water intrusion
-

4. Waterline Tile Replacement

- Carefully remove existing waterline tile around the perimeter of the pool. Removal will include chipping away the existing mortar and preparing the surface for new tile installation.
 - Clean and prep the exposed bond beam to create a proper bonding surface for the new tile. Any loose material will be removed to allow proper adhesion.
 - Install new **6" x 6" waterline tile** selected by the client from the tile options provided. Tile will be installed evenly along the pool waterline using appropriate pool-grade thinset mortar.
 -
 - Apply pool-grade grout between all tile joints and clean the tile surface to achieve a uniform and finished appearance.
-

5. Pool Interior Preparation

- Drain pool completely
 - Perform surface inspection of existing plaster and shell condition
 - Clean pool interior and prepare surfaces for resurfacing
 - Apply bond coat (primer) prior to new plaster installation
-

6. Full Pool Replaster- Mini Pebble Finish

- Install mini-pebble plaster finish throughout entire pool interior
 - Properly trowel and finish plaster to manufacturer specifications
 - Perform acid wash and final cleanup
 - Coordinate pool refill and initial startup process
-

KBF

SignNow e-signature ID: 162e9a05a5...
03/20/2026 12:53:49 UTC

Pool Remodeling Service Agreement

This agreement is made between BackYard Solutions Group and Keneddie Felarca for pool remodeling services to be performed at the following address:

Project Location: 3008 Vanderbilt Dr, Flower Mound, TX 75022, USA

Project Start Date: **MON 03/23/2026**

KBF

SignNow e-signature ID: 4ed17dc0b7...
03/20/2026 12:53:49 UTC

Payment Terms

- Total Project Cost: \$17,975.00
- 50% deposit due at beginning of project: \$8,987.50 // 03/23/2026
- Remaining 50% due upon project completion: \$8,987.50 // TBD
- Accepted forms of payment: Cash, check,

KBF

SignNow e-signature ID: 0c1cbfc57b...
03/20/2026 12:53:49 UTC

Change Orders

Any modifications to the original scope of work must be submitted in writing and may result in additional charges and extended timelines.

Client Responsibilities

- Client is responsible for obtaining HOA approval before the project begins.
(Let us know if you need assistance getting approval from your HOA)

- BackYard Solutions Group, is not liable for delays or rework due to unapproved designs or denied HOA applications.
- Clear access to the job site and working water/electrical supply must be provided.

Weather Delays

Weather-related delays may extend the project completion timeline. Clients will be informed promptly of any rescheduling due to weather.

Clean-Up and Final Walkthrough

Upon completion, our team will perform a final clean-up and walkthrough with the client to ensure satisfaction before final payment is collected.

Termination Clause

Either party may terminate this agreement with written notice. In such cases, Client agrees to pay for all completed work and any materials ordered or delivered.

kbfelarca



(Client Signature)

03/20/2026

Date